



**CITY OF CAMPBELL**  
**Community Development Department**

January 17, 2020

**NOTICE OF PUBLIC HEARING**

Notice is hereby given that the Planning Commission of the City of Campbell has set the time of 7:30 p.m., or shortly thereafter, on Tuesday, **January 28, 2020**, in the City Hall Council Chambers, 70 North First Street, Campbell, California, for a Public Hearing to consider the application of Susan Chen for a Site and Architectural Review Permit (PLN2019-123) to allow the construction of a new approximately 4,357 square-foot two-story single-family residence on property located at **1420 Van Dusen Lane**. Staff is recommending that this item be deemed Categorical Exempt under CEQA.

Interested persons may appear and be heard at this hearing. Please be advised that if you challenge the nature of the above project in court, you may be limited to raising only those issues you or someone else raised at the Public Hearing described in this Notice, or in written correspondence delivered to the City of Campbell Planning Commission at, or prior to, the Public Hearing. Questions may be addressed to the Community Development Department at (408) 866-2140.

Plans and architectural drawings may be viewed at the Planning Division office during normal business hours (8:00 a.m. – 5:00 p.m.) and on the City's 'Public Notices' web page (<http://www.cityofcampbell.com/501/Public-Notices>) under 'Planning Commission'.

Decisions of the Planning Commission may be appealed to the City Council. Appeals must be submitted to the City Clerk in writing within 10 calendar days of an action by the Commission.



In compliance with the Americans with Disabilities Act, the City of Campbell will generally, upon request, provide appropriate aids and services leading to effective communication for qualified persons with disabilities so they can participate equally in the public hearings, including qualified sign language interpreters, listening assistive devices, and other ways of making information and communications accessible to people who have speech, hearing, or vision impairments. Anyone who requires auxiliary aid or service for effective communication should contact the City Clerk's Office at 70 N. First Street, Campbell, CA 95008, (408) 866-2117 or [ClerksOffice@campbellca.gov](mailto:ClerksOffice@campbellca.gov) at least one week prior to the meeting. Hearing impaired or TTY/TDD text telephones users may contact the City by dialing 711 for California Relay Service (CRS) or by telephoning any other service providers' CRS telephone number.

PLANNING COMMISSION  
CITY OF CAMPBELL  
PAUL KERMOYAN  
SECRETARY

PLEASE NOTE: When calling about this Notice,  
please refer to: **1420 Van Dusen Lane**



# 1420 Van Dusen Ln



This map is based on GIS Information and reflects the most current information at the time of this printing. The map is intended for reference purposes only and the City and its staff is not responsible for errors.



1420 VAN DUSEN LANE CAMPBELL, CA 95008


PROJECT INFORMATION		SHEET INDEX		MISCELLANEOUS NOTES																																																																			
VICINITY MAP		ARCHITECTURAL		FIRE DEPARTMENT NOTES																																																																			
		<table border="1"> <tr> <th>FRONT:</th> <th>REQUIRED</th> <th>PROPOSED</th> </tr> <tr> <td>FRONT 1ST FLOOR:</td> <td>20'-0"</td> <td>25'-0"</td> </tr> <tr> <td>FRONT 2ND FLOOR:</td> <td>20'-0"</td> <td>25'-0"</td> </tr> <tr> <th>SIDE:</th> <td></td> <td></td> </tr> <tr> <td>LEFT-SIDE 1ST FLOOR:</td> <td>8'-0"</td> <td>11'-6"</td> </tr> <tr> <td>LEFT-SIDE 2ND FLOOR:</td> <td>8'-0"</td> <td>13'-6"</td> </tr> <tr> <td>RIGHT-SIDE 1ST FLOOR:</td> <td>10'-0"</td> <td>11'-10"</td> </tr> <tr> <td>RIGHT-SIDE 2ND FLOOR:</td> <td>10'-0"</td> <td>11'-10"</td> </tr> <tr> <th>REAR:</th> <td></td> <td></td> </tr> <tr> <td>REAR 1ST FLOOR:</td> <td>25'-0"</td> <td>96'-10"</td> </tr> <tr> <td>REAR 2ND FLOOR:</td> <td>25'-0"</td> <td>96'-10"</td> </tr> <tr> <th>MAXIMUM HEIGHT:</th> <th>REQUIRED</th> <th>PROPOSED</th> </tr> <tr> <td></td> <td>28'-0"</td> <td>27'-9"</td> </tr> </table>		FRONT:	REQUIRED	PROPOSED	FRONT 1ST FLOOR:	20'-0"	25'-0"	FRONT 2ND FLOOR:	20'-0"	25'-0"	SIDE:			LEFT-SIDE 1ST FLOOR:	8'-0"	11'-6"	LEFT-SIDE 2ND FLOOR:	8'-0"	13'-6"	RIGHT-SIDE 1ST FLOOR:	10'-0"	11'-10"	RIGHT-SIDE 2ND FLOOR:	10'-0"	11'-10"	REAR:			REAR 1ST FLOOR:	25'-0"	96'-10"	REAR 2ND FLOOR:	25'-0"	96'-10"	MAXIMUM HEIGHT:	REQUIRED	PROPOSED		28'-0"	27'-9"	<table border="1"> <tr> <th>ARCHITECTURAL</th> </tr> <tr> <td>A-00 COVER SHEET</td> </tr> <tr> <td>A-01 TOPOGRAPHIC SURVEY</td> </tr> <tr> <td>A-10 PROPOSED SITE PLAN &amp; SITE PHOTOGRAPH</td> </tr> <tr> <td>A-11 EXISTING &amp; PROPOSED STREETSCAPES / FLOOR AREA DIAGRAMS</td> </tr> <tr> <td>A-20 PROPOSED FIRST FLOOR PLANS</td> </tr> <tr> <td>A-21 PROPOSED SECOND FLOOR PLANS</td> </tr> <tr> <td>A-30 PROPOSED FRONT &amp; LEFT ELEVATIONS</td> </tr> <tr> <td>A-31 PROPOSED REAR &amp; RIGHT ELEVATIONS</td> </tr> <tr> <td>A-40 SECTIONS</td> </tr> <tr> <th>CIVIL</th> </tr> <tr> <td>1 TITLE SHEET</td> </tr> <tr> <td>2 TOPOGRAPHIC SURVEY AND DEMOLITION PLAN</td> </tr> <tr> <td>3 GRADING AND DRAINAGE PLAN</td> </tr> <tr> <td>4 COMPOSITE UTILITY &amp; STORMWATER MGT. PLAN</td> </tr> <tr> <td>5 EROSION CONTROL DETAILS-SHEET 1</td> </tr> <tr> <td>6 EROSION CONTROL DETAILS-SHEET 2</td> </tr> <tr> <td>7 EROSION CONTROL PLAN</td> </tr> <tr> <td>8 BLUE PRINT FOR A CLEAN BAY</td> </tr> <tr> <th>LANDSCAPING</th> </tr> <tr> <td>L1 MASTER PLANTING PLAN</td> </tr> <tr> <td>L2 COVERAGE AND HYDRAZONE PLANS</td> </tr> <tr> <td>L3 IRRIGATION PLAN</td> </tr> </table>		ARCHITECTURAL	A-00 COVER SHEET	A-01 TOPOGRAPHIC SURVEY	A-10 PROPOSED SITE PLAN & SITE PHOTOGRAPH	A-11 EXISTING & PROPOSED STREETSCAPES / FLOOR AREA DIAGRAMS	A-20 PROPOSED FIRST FLOOR PLANS	A-21 PROPOSED SECOND FLOOR PLANS	A-30 PROPOSED FRONT & LEFT ELEVATIONS	A-31 PROPOSED REAR & RIGHT ELEVATIONS	A-40 SECTIONS	CIVIL	1 TITLE SHEET	2 TOPOGRAPHIC SURVEY AND DEMOLITION PLAN	3 GRADING AND DRAINAGE PLAN	4 COMPOSITE UTILITY & STORMWATER MGT. PLAN	5 EROSION CONTROL DETAILS-SHEET 1	6 EROSION CONTROL DETAILS-SHEET 2	7 EROSION CONTROL PLAN	8 BLUE PRINT FOR A CLEAN BAY	LANDSCAPING	L1 MASTER PLANTING PLAN	L2 COVERAGE AND HYDRAZONE PLANS	L3 IRRIGATION PLAN	<p>1- A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN THE SINGLE FAMILY RESIDENCE STRUCTURE; SHALL BE IN ACCORDANCE WITH NFPA 13D AND STATE AND LOCAL REQUIREMENTS.</p> <p>2- CONTACT CITY OF CAMPBELL UTILITIES (CWG) AND SUBMIT A UTILITY APPLICATION WHICH INCLUDES 40 GPM FOR FIRE SPRINKLER DEMAND. WATER METER SIZE NEEDS TO BE DETERMINED BY WORK PRIOR TO FIRE DEPARTMENT APPROVAL.</p> <p>3- FOR PLACEMENT OF SMOKE ALARMS &amp; CARBON MONOXIDE ALARMS IN ROOMS WITH VARIATIONS IN CEILING HEIGHTS (SLOPED, PITCHED ETC.), REFER TO THE MANUFACTURERS GUIDELINES FOR PROPER PLACEMENT.</p> <p>4- FIRE SPRINKLER SYSTEM TO BE APPROVED UNDER A SEPARATE PERMIT.</p>		<p>1. WORKING HOURS: No work shall commence on the job site prior to 8:00 a.m. nor continue later than 6:00 p.m., Monday through Friday, 9:00 a.m. nor continue later than 6:00 p.m. Saturday &amp; 9:00 a.m. - 5:00 PM on Sunday &amp; Holidays.</p> <p>2. General Contractor shall verify all underground utility locations prior to excavation, trenching or grading of any kind. General Contractor shall coordinate w/ applicable utility companies when rerouting electrical, telephone, cable TV, gas, water, sanitary sewer services or any other utility. G.C. shall maintain all electrical &amp; communication systems in House at all times.</p> <p>3. All work is to be performed in accordance w/ all governing codes, ordinances &amp; regulations. G.C. shall become familiar w/all city of Burlingame aspects of working. General contractor shall be responsible for coordination &amp; execution of the work shown or implied in the construction documents &amp; is responsible for construction means, methods &amp; procedures.</p> <p>4. General Contractor shall coordinate all facets of his work &amp; all trades involved to avoid conflict in the location, installation &amp; construction of all items of work as indicated on the construction documents. If any work is to be installed by the Owner's work must be made. Coordinate with Architect / Owner.</p> <p>5. General Contractor shall leave the job site "broom clean" at the end of each working day. All materials shall be stored in a neat &amp; safe place to avoid accidents, for construction &amp; for the owner.</p> <p>6. In case of any discrepancy in the contract documents, consult the Architect before proceeding.</p> <p>7. No dimensions shall be taken by scaling from the drawings. Details take precedence over general sections or floor plans. If dimensions must be clarified, consult the Architect. Refer to the Cover Sheet for dimensioning standards.</p> <p>8. Verify all dimensions on the job site prior to ordering or manufacturing.</p> <p>9. General Contractor shall review all architectural drawings before framing. Coordinate recessed light fixture locations, shafts &amp; HVAC ductwork prior to framing. It is imperative that framing member locations do not conflict w/ locations of recessed light fixtures. If conflict exists, notify architect.</p> <p>10. General Contractor shall install all appliances specified &amp; all new equipment according to manufacturer's instructions. All guarantees, instruction booklets &amp; information regarding new equipment shall be handed directly to the Owner in one manila envelope at the time of substantial completion. Contractor shall verify that every piece of equipment &amp; every appliance is in perfect working order &amp; that information about all warranties &amp; guarantees is made known to the Owner.</p> <p>11. The installer of each major unit of work is required to inspect the substrate and conditions to receive work &amp; shall report all unsatisfactory conditions to the General Contractor &amp; not proceed until satisfactory conditions are attained.</p> <p>12. For mounting heights not clearly outlined in the plans or schedules, coordinate w/ the Architect. Architect shall confirm all electrical device &amp; light fixture locations before Contractor pulls wire.</p> <p>13. Provide solid blocking as necessary for wall mounted shelves, fixtures &amp; fittings, even when work is to be done by Owner directly. Review scope of work &amp; locations from interior elevations &amp; coordinate w/ Owner/Architect.</p> <p>14. All fastening devices to be concealed unless otherwise shown.</p> <p>15. Weather-strip all exterior doors &amp; windows.</p> <p>16. Caulk or otherwise seal around all openings to limit infiltration, including but not limited to Exterior Joints around windows &amp; door frames, between sole plates, floors &amp; between exterior wall panels.</p> <p>17. General Contractor shall verify that all work on the exterior of the project is watertight. All joints exposed to the elements shall be tested for water tightness prior to substantial completion.</p> <p>18. A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN THE SINGLE FAMILY RESIDENCE STRUCTURE.</p>	
FRONT:	REQUIRED	PROPOSED																																																																					
FRONT 1ST FLOOR:	20'-0"	25'-0"																																																																					
FRONT 2ND FLOOR:	20'-0"	25'-0"																																																																					
SIDE:																																																																							
LEFT-SIDE 1ST FLOOR:	8'-0"	11'-6"																																																																					
LEFT-SIDE 2ND FLOOR:	8'-0"	13'-6"																																																																					
RIGHT-SIDE 1ST FLOOR:	10'-0"	11'-10"																																																																					
RIGHT-SIDE 2ND FLOOR:	10'-0"	11'-10"																																																																					
REAR:																																																																							
REAR 1ST FLOOR:	25'-0"	96'-10"																																																																					
REAR 2ND FLOOR:	25'-0"	96'-10"																																																																					
MAXIMUM HEIGHT:	REQUIRED	PROPOSED																																																																					
	28'-0"	27'-9"																																																																					
ARCHITECTURAL																																																																							
A-00 COVER SHEET																																																																							
A-01 TOPOGRAPHIC SURVEY																																																																							
A-10 PROPOSED SITE PLAN & SITE PHOTOGRAPH																																																																							
A-11 EXISTING & PROPOSED STREETSCAPES / FLOOR AREA DIAGRAMS																																																																							
A-20 PROPOSED FIRST FLOOR PLANS																																																																							
A-21 PROPOSED SECOND FLOOR PLANS																																																																							
A-30 PROPOSED FRONT & LEFT ELEVATIONS																																																																							
A-31 PROPOSED REAR & RIGHT ELEVATIONS																																																																							
A-40 SECTIONS																																																																							
CIVIL																																																																							
1 TITLE SHEET																																																																							
2 TOPOGRAPHIC SURVEY AND DEMOLITION PLAN																																																																							
3 GRADING AND DRAINAGE PLAN																																																																							
4 COMPOSITE UTILITY & STORMWATER MGT. PLAN																																																																							
5 EROSION CONTROL DETAILS-SHEET 1																																																																							
6 EROSION CONTROL DETAILS-SHEET 2																																																																							
7 EROSION CONTROL PLAN																																																																							
8 BLUE PRINT FOR A CLEAN BAY																																																																							
LANDSCAPING																																																																							
L1 MASTER PLANTING PLAN																																																																							
L2 COVERAGE AND HYDRAZONE PLANS																																																																							
L3 IRRIGATION PLAN																																																																							
GENERAL INFORMATION		FLOOR AREA CALCULATION		GENERAL NOTES																																																																			
<table border="1"> <tr> <td>PROPERTY ADDRESS:</td> <td>1420 VAN DUSEN LANE, CAMPBELL, CA, 95008</td> </tr> <tr> <td>APN:</td> <td>403-19-025</td> </tr> <tr> <td>DESCRIPTION OF WORK:</td> <td>NEW 2-STORY HOUSE W/ ATTACHED GARAGE</td> </tr> <tr> <td>ZONING:</td> <td>R-1-9</td> </tr> <tr> <td>OCCUPANCY GROUP:</td> <td>R-3/U</td> </tr> <tr> <td>TYPE OF CONSTRUCTION:</td> <td>TYPE V-B</td> </tr> </table>		PROPERTY ADDRESS:	1420 VAN DUSEN LANE, CAMPBELL, CA, 95008	APN:	403-19-025	DESCRIPTION OF WORK:	NEW 2-STORY HOUSE W/ ATTACHED GARAGE	ZONING:	R-1-9	OCCUPANCY GROUP:	R-3/U	TYPE OF CONSTRUCTION:	TYPE V-B	<table border="1"> <tr> <th>EXISTING:</th> <th>PROPOSED PROJECT:</th> </tr> <tr> <td>(C) SITE AREA</td> <td>13277 SQ. FT.</td> </tr> <tr> <td>(2) LIVING</td> <td>961 SQ. FT.</td> </tr> <tr> <td>PROPOSED 1ST FLOOR LIVING AREA</td> <td>1,915 SQ. FT.</td> </tr> <tr> <td>PROPOSED 2ND FLOOR LIVING AREA</td> <td>1,984 SQ. FT.</td> </tr> <tr> <td>PROPOSED 1ST &amp; 2ND FLOOR LIVING AREA TOTAL:</td> <td>3,899 SQ. FT.</td> </tr> <tr> <td>PROPOSED GARAGE</td> <td>458 SQ. FT.</td> </tr> <tr> <td>PROPOSED BUILDING AREA TOTAL:</td> <td>4,357 SQ. FT.</td> </tr> </table>		EXISTING:	PROPOSED PROJECT:	(C) SITE AREA	13277 SQ. FT.	(2) LIVING	961 SQ. FT.	PROPOSED 1ST FLOOR LIVING AREA	1,915 SQ. FT.	PROPOSED 2ND FLOOR LIVING AREA	1,984 SQ. FT.	PROPOSED 1ST & 2ND FLOOR LIVING AREA TOTAL:	3,899 SQ. FT.	PROPOSED GARAGE	458 SQ. FT.	PROPOSED BUILDING AREA TOTAL:	4,357 SQ. FT.	<p>1. WORKING HOURS: No work shall commence on the job site prior to 8:00 a.m. nor continue later than 6:00 p.m., Monday through Friday, 9:00 a.m. nor continue later than 6:00 p.m. Saturday &amp; 9:00 a.m. - 5:00 PM on Sunday &amp; Holidays.</p> <p>2. General Contractor shall verify all underground utility locations prior to excavation, trenching or grading of any kind. General Contractor shall coordinate w/ applicable utility companies when rerouting electrical, telephone, cable TV, gas, water, sanitary sewer services or any other utility. G.C. shall maintain all electrical &amp; communication systems in House at all times.</p> <p>3. All work is to be performed in accordance w/ all governing codes, ordinances &amp; regulations. G.C. shall become familiar w/all city of Burlingame aspects of working. General contractor shall be responsible for coordination &amp; execution of the work shown or implied in the construction documents &amp; is responsible for construction means, methods &amp; procedures.</p> <p>4. General Contractor shall coordinate all facets of his work &amp; all trades involved to avoid conflict in the location, installation &amp; construction of all items of work as indicated on the construction documents. If any work is to be installed by the Owner's work must be made. Coordinate with Architect / Owner.</p> <p>5. General Contractor shall leave the job site "broom clean" at the end of each working day. All materials shall be stored in a neat &amp; safe place to avoid accidents, for construction &amp; for the owner.</p> <p>6. In case of any discrepancy in the contract documents, consult the Architect before proceeding.</p> <p>7. No dimensions shall be taken by scaling from the drawings. Details take precedence over general sections or floor plans. If dimensions must be clarified, consult the Architect. Refer to the Cover Sheet for dimensioning standards.</p> <p>8. Verify all dimensions on the job site prior to ordering or manufacturing.</p> <p>9. General Contractor shall review all architectural drawings before framing. Coordinate recessed light fixture locations, shafts &amp; HVAC ductwork prior to framing. It is imperative that framing member locations do not conflict w/ locations of recessed light fixtures. If conflict exists, notify architect.</p> <p>10. General Contractor shall install all appliances specified &amp; all new equipment according to manufacturer's instructions. All guarantees, instruction booklets &amp; information regarding new equipment shall be handed directly to the Owner in one manila envelope at the time of substantial completion. Contractor shall verify that every piece of equipment &amp; every appliance is in perfect working order &amp; that information about all warranties &amp; guarantees is made known to the Owner.</p> <p>11. The installer of each major unit of work is required to inspect the substrate and conditions to receive work &amp; shall report all unsatisfactory conditions to the General Contractor &amp; not proceed until satisfactory conditions are attained.</p> <p>12. For mounting heights not clearly outlined in the plans or schedules, coordinate w/ the Architect. Architect shall confirm all electrical device &amp; light fixture locations before Contractor pulls wire.</p> <p>13. Provide solid blocking as necessary for wall mounted shelves, fixtures &amp; fittings, even when work is to be done by Owner directly. Review scope of work &amp; locations from interior elevations &amp; coordinate w/ Owner/Architect.</p> <p>14. All fastening devices to be concealed unless otherwise shown.</p> <p>15. Weather-strip all exterior doors &amp; windows.</p> <p>16. Caulk or otherwise seal around all openings to limit infiltration, including but not limited to Exterior Joints around windows &amp; door frames, between sole plates, floors &amp; between exterior wall panels.</p> <p>17. General Contractor shall verify that all work on the exterior of the project is watertight. All joints exposed to the elements shall be tested for water tightness prior to substantial completion.</p> <p>18. A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN THE SINGLE FAMILY RESIDENCE STRUCTURE.</p>																																							
PROPERTY ADDRESS:	1420 VAN DUSEN LANE, CAMPBELL, CA, 95008																																																																						
APN:	403-19-025																																																																						
DESCRIPTION OF WORK:	NEW 2-STORY HOUSE W/ ATTACHED GARAGE																																																																						
ZONING:	R-1-9																																																																						
OCCUPANCY GROUP:	R-3/U																																																																						
TYPE OF CONSTRUCTION:	TYPE V-B																																																																						
EXISTING:	PROPOSED PROJECT:																																																																						
(C) SITE AREA	13277 SQ. FT.																																																																						
(2) LIVING	961 SQ. FT.																																																																						
PROPOSED 1ST FLOOR LIVING AREA	1,915 SQ. FT.																																																																						
PROPOSED 2ND FLOOR LIVING AREA	1,984 SQ. FT.																																																																						
PROPOSED 1ST & 2ND FLOOR LIVING AREA TOTAL:	3,899 SQ. FT.																																																																						
PROPOSED GARAGE	458 SQ. FT.																																																																						
PROPOSED BUILDING AREA TOTAL:	4,357 SQ. FT.																																																																						
SITE CONTEXT		MAXIMUM ALLOWABLE LOT COVERAGE:		GENERAL NOTES																																																																			
<p>THE LOT IS 90' WIDE BY APPROXIMATELY 17814' DEEP AND LOCATED MID-BLOCK IN VAN DUSEN LANE</p>		<table border="1"> <tr> <td>13277 SQ.FT. X .45 =</td> <td>5,975 SQ. FT.</td> </tr> <tr> <td>LOT COVERAGE:</td> <td></td> </tr> </table>		13277 SQ.FT. X .45 =	5,975 SQ. FT.	LOT COVERAGE:		<p>1. WORKING HOURS: No work shall commence on the job site prior to 8:00 a.m. nor continue later than 6:00 p.m., Monday through Friday, 9:00 a.m. nor continue later than 6:00 p.m. Saturday &amp; 9:00 a.m. - 5:00 PM on Sunday &amp; Holidays.</p> <p>2. General Contractor shall verify all underground utility locations prior to excavation, trenching or grading of any kind. General Contractor shall coordinate w/ applicable utility companies when rerouting electrical, telephone, cable TV, gas, water, sanitary sewer services or any other utility. G.C. shall maintain all electrical &amp; communication systems in House at all times.</p> <p>3. All work is to be performed in accordance w/ all governing codes, ordinances &amp; regulations. G.C. shall become familiar w/all city of Burlingame aspects of working. General contractor shall be responsible for coordination &amp; execution of the work shown or implied in the construction documents &amp; is responsible for construction means, methods &amp; procedures.</p> <p>4. General Contractor shall coordinate all facets of his work &amp; all trades involved to avoid conflict in the location, installation &amp; construction of all items of work as indicated on the construction documents. If any work is to be installed by the Owner's work must be made. Coordinate with Architect / Owner.</p> <p>5. General Contractor shall leave the job site "broom clean" at the end of each working day. All materials shall be stored in a neat &amp; safe place to avoid accidents, for construction &amp; for the owner.</p> <p>6. In case of any discrepancy in the contract documents, consult the Architect before proceeding.</p> <p>7. No dimensions shall be taken by scaling from the drawings. Details take precedence over general sections or floor plans. If dimensions must be clarified, consult the Architect. Refer to the Cover Sheet for dimensioning standards.</p> <p>8. Verify all dimensions on the job site prior to ordering or manufacturing.</p> <p>9. General Contractor shall review all architectural drawings before framing. Coordinate recessed light fixture locations, shafts &amp; HVAC ductwork prior to framing. It is imperative that framing member locations do not conflict w/ locations of recessed light fixtures. If conflict exists, notify architect.</p> <p>10. General Contractor shall install all appliances specified &amp; all new equipment according to manufacturer's instructions. All guarantees, instruction booklets &amp; information regarding new equipment shall be handed directly to the Owner in one manila envelope at the time of substantial completion. Contractor shall verify that every piece of equipment &amp; every appliance is in perfect working order &amp; that information about all warranties &amp; guarantees is made known to the Owner.</p> <p>11. The installer of each major unit of work is required to inspect the substrate and conditions to receive work &amp; shall report all unsatisfactory conditions to the General Contractor &amp; not proceed until satisfactory conditions are attained.</p> <p>12. For mounting heights not clearly outlined in the plans or schedules, coordinate w/ the Architect. Architect shall confirm all electrical device &amp; light fixture locations before Contractor pulls wire.</p> <p>13. Provide solid blocking as necessary for wall mounted shelves, fixtures &amp; fittings, even when work is to be done by Owner directly. Review scope of work &amp; locations from interior elevations &amp; coordinate w/ Owner/Architect.</p> <p>14. All fastening devices to be concealed unless otherwise shown.</p> <p>15. Weather-strip all exterior doors &amp; windows.</p> <p>16. Caulk or otherwise seal around all openings to limit infiltration, including but not limited to Exterior Joints around windows &amp; door frames, between sole plates, floors &amp; between exterior wall panels.</p> <p>17. General Contractor shall verify that all work on the exterior of the project is watertight. All joints exposed to the elements shall be tested for water tightness prior to substantial completion.</p> <p>18. A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN THE SINGLE FAMILY RESIDENCE STRUCTURE.</p>																																																															
13277 SQ.FT. X .45 =	5,975 SQ. FT.																																																																						
LOT COVERAGE:																																																																							
CODES AND REGULATIONS		MAXIMUM ALLOWABLE LOT COVERAGE:		GENERAL NOTES																																																																			
<p>ALL WORK TO COMPLY WITH THE 2016 C.R.C., C.B.C., C.M.C. &amp; C.P.C., CALIFORNIA TITLE 24 AMENDMENTS AND CITY OF CAMPBELL MUNICIPAL CODE.</p> <p>BUILDING CODE USED TO PERFORM THE WORK ACCORDING TO THE BUILDING CODES, ORDINANCES AND LAWS OF THE AUTHORITY HAVING JURISDICTION TO THE PROJECT WHICH INCLUDE BUT RE NOT LIMITED TO:</p> <p>A. 2016 CALIFORNIA BUILDING CODE          B. 2016 CALIFORNIA RESIDENTIAL CODE          C. 2016 CALIFORNIA MECHANICAL CODE          D. 2016 CALIFORNIA PLUMBING CODE          E. 2016 CALIFORNIA ELECTRICAL CODE          F. 2016 CALIFORNIA FIRE CODE          G. 2016 CALIFORNIA GREEN BUILDING STANDARD CODE          H. 2016 CALIFORNIA ENERGY CODE          I. CITY OF CAMPBELL MUNICIPAL CODE          J. CAMPBELL GREEN BUILDING ORDINANCE</p>		<table border="1"> <tr> <td>13277 SQ.FT. X .35 =</td> <td>4646.95 SQ. FT.</td> </tr> </table>		13277 SQ.FT. X .35 =	4646.95 SQ. FT.	<p>1. WORKING HOURS: No work shall commence on the job site prior to 8:00 a.m. nor continue later than 6:00 p.m., Monday through Friday, 9:00 a.m. nor continue later than 6:00 p.m. Saturday &amp; 9:00 a.m. - 5:00 PM on Sunday &amp; Holidays.</p> <p>2. General Contractor shall verify all underground utility locations prior to excavation, trenching or grading of any kind. General Contractor shall coordinate w/ applicable utility companies when rerouting electrical, telephone, cable TV, gas, water, sanitary sewer services or any other utility. G.C. shall maintain all electrical &amp; communication systems in House at all times.</p> <p>3. All work is to be performed in accordance w/ all governing codes, ordinances &amp; regulations. G.C. shall become familiar w/all city of Burlingame aspects of working. General contractor shall be responsible for coordination &amp; execution of the work shown or implied in the construction documents &amp; is responsible for construction means, methods &amp; procedures.</p> <p>4. General Contractor shall coordinate all facets of his work &amp; all trades involved to avoid conflict in the location, installation &amp; construction of all items of work as indicated on the construction documents. If any work is to be installed by the Owner's work must be made. Coordinate with Architect / Owner.</p> <p>5. General Contractor shall leave the job site "broom clean" at the end of each working day. All materials shall be stored in a neat &amp; safe place to avoid accidents, for construction &amp; for the owner.</p> <p>6. In case of any discrepancy in the contract documents, consult the Architect before proceeding.</p> <p>7. No dimensions shall be taken by scaling from the drawings. Details take precedence over general sections or floor plans. If dimensions must be clarified, consult the Architect. Refer to the Cover Sheet for dimensioning standards.</p> <p>8. Verify all dimensions on the job site prior to ordering or manufacturing.</p> <p>9. General Contractor shall review all architectural drawings before framing. Coordinate recessed light fixture locations, shafts &amp; HVAC ductwork prior to framing. It is imperative that framing member locations do not conflict w/ locations of recessed light fixtures. If conflict exists, notify architect.</p> <p>10. General Contractor shall install all appliances specified &amp; all new equipment according to manufacturer's instructions. All guarantees, instruction booklets &amp; information regarding new equipment shall be handed directly to the Owner in one manila envelope at the time of substantial completion. Contractor shall verify that every piece of equipment &amp; every appliance is in perfect working order &amp; that information about all warranties &amp; guarantees is made known to the Owner.</p> <p>11. The installer of each major unit of work is required to inspect the substrate and conditions to receive work &amp; shall report all unsatisfactory conditions to the General Contractor &amp; not proceed until satisfactory conditions are attained.</p> <p>12. For mounting heights not clearly outlined in the plans or schedules, coordinate w/ the Architect. Architect shall confirm all electrical device &amp; light fixture locations before Contractor pulls wire.</p> <p>13. Provide solid blocking as necessary for wall mounted shelves, fixtures &amp; fittings, even when work is to be done by Owner directly. Review scope of work &amp; locations from interior elevations &amp; coordinate w/ Owner/Architect.</p> <p>14. All fastening devices to be concealed unless otherwise shown.</p> <p>15. Weather-strip all exterior doors &amp; windows.</p> <p>16. Caulk or otherwise seal around all openings to limit infiltration, including but not limited to Exterior Joints around windows &amp; door frames, between sole plates, floors &amp; between exterior wall panels.</p> <p>17. General Contractor shall verify that all work on the exterior of the project is watertight. All joints exposed to the elements shall be tested for water tightness prior to substantial completion.</p> <p>18. A RESIDENTIAL FIRE SPRINKLER SYSTEM IS REQUIRED IN THE SINGLE FAMILY RESIDENCE STRUCTURE.</p>																																																																	
13277 SQ.FT. X .35 =	4646.95 SQ. FT.																																																																						

ISSUED: 07/23/19

PROJECT NO: 1822 DATE: 10/16/19

COVERSHEET

A-0.0



**BASIS OF BEARINGS**  
 THE BEARING N76°45'20"E OF ROBNIK AVE PER  
 PM 605 M 48  
 SANTA CLARA COUNTY RECORDS

**LOT AREA**  
 13,277 SQ. FT.±

SHEET	1	OF	1
VAN DUSEN 18-01	1"=10'	PROJECT	KA
SCALE:		DATE:	12-07-18
DATE:			

**TOPOGRAPHIC - BOUNDARY SITE PLAN**  
 1420 VAN DUSEN LANE, CAMPBELL, CA 95008  
 DOC NO. 23926057  
 APN 403-19-025  
 SANTA CLARA COUNTY, CALIFORNIA



**BAY LAND CONSULTING**  
 LAND SURVEYORS/CIVIL ENGINEERS  
 2107 N. 1ST ST.  
 SANTA CLARA, CA 95050  
 PH: (408) 766-6700  
 MAPPING THE BAY AREA




**UNDERGROUND UTILITY NOTE**  
 ALL UNDERGROUND UTILITY LINES MAY NOT BE SHOWN HEREON, BUT MAY EXIST AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE SIZE, DEPTH, LOCATION THEREOF  
**CALL 811 BEFORE YOU DIG**

**EASEMENTS**  
 IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE ANY CONFLICTS WITH ANY EASEMENTS. EASEMENTS IF ANY ARE NOT INDICATED HEREON

**CITY BENCHMARK NO. 3**  
 THE ELEVATIONS SHOWN HEREON ARE PER CITY OF CAMPBELL BM NO. 3 BRASS DISC ON TOP CURB AT S/E CORNER OF MORE AND POLLARD AVE  
 BM ELEV TAKEN AS 280.08 CITY DATUM

**T.B.M.**  
 TOP OF SSMH  
 RIM ELEV=258.00

TOPOGRAPHY SURVEY



EXISTING FIR TREE TO REMAIN



EXISTING FIR TREE TO BE REMOVED





EXISTING UNKNOWN TREE SPECIES (NOT ASH, CEDAR, OAK OR REDWOOD) TO REMAIN



EXISTING BLACK WALNUT TREE TO REMAIN



EXISTING INCENSE CEDAR TREE (CYPRESS) TO BE REMOVED



2 EXISTING TREE OF HEAVEN TO BE REMOVED

HouseWorth Company LLC

1420 VAN DUSEN LANE, CAMPBELL, CA 95008



20370 TOWN CENTER LN SUITE 139 CUPERTINO, CA 95014 (408) 862-0977

APN 403-19-092  
1378 ROBNICK COURT

APN 403-19-0  
1403 HARRIET COURT

LEGEND	
FIRST FLOOR ROOF PLAN	
SECOND FLOOR ROOF PLAN	
FIRST FLOOR EXTERIOR WALL	
SECOND FLOOR EXTERIOR WALL	
EXISTING BUILDING	
NEIGHBOR BUILDING	

DATE: 07/03/19

PROJECT NO: 1822 DATE: 10/16/19

PROPOSED SITE PLAN

A-1.0


PROPOSED SITE PLAN AND SITE PHOTOGRAPHS

1/8" 1




2ND FLOOR AREA CALCULATION	
1) 11'-10" X 12'-5"	147 SF
2) 11'-6" X 14'-5"	166 SF
3) 14'-4" X 11'-5"	165 SF
4) 14'-4" X 20'-1"	288 SF
5) 9'-0" X 19'-1"	172 SF
6) 14'-4" X 26'-5"	380 SF
7) 7'-8" X 17'-10"	83 SF
8) 13'-9" X 13'-7"	187 SF
9) 7'-1" X 7'-5"	52 SF
10) 16'-3" X 21'-1"	343 SF
<b>2ND FLOOR LIVING AREA TOTAL:</b>	<b>1,984 SF</b>

1ST FLOOR LIVING AREA:	1,915 SF
2ND FLOOR LIVING AREA:	1,984 SF
1ST & 2ND FLOOR LIVING AREA TOTAL:	3,899 SF
GARAGE FLOOR AREA:	458 SF
BUILDING AREA TOTAL:	4,357 SF



1ST FLOOR AREA CALCULATION	
A) 20'-9" X 13'-10"	287 SF
B) 37'-8" X 14'-10"	549 SF
C) 23'-11" X 16'-5"	387 SF
D) 23'-11" X 19'-5"	461 SF
E) 4'-1" X 11'-0"	45 SF
F) 13'-3" X 3'-3" / 2	5 SF
G) 3'-3" X 4'-7"	15 SF
H) 9'-3" X 3'-3" / 2	8 SF
J) 23'-11" X 13'-6"	321 SF
1ST FLOOR LIVING AREA TOTAL:	1,915 SF
GARAGE :	
K) 21'-10" X 21'-0"	458 SF
1ST FLOOR AREA TOTAL:	2,373 SF



SECOND FLOOR AREA DIAGRAM

1/8" 4

FIRST FLOOR AREA DIAGRAM

1/8" 3




EXISTING STREETSCAPE

NTS 2



PROPOSED STREETSCAPE

NTS 1



HouseWorth  
Company  
LLC

1420 VAN DUSEN LANE,  
CAMPBELL, CA 95008



20370 TOWN CENTER LN  
SUITE 139  
CUPERTINO, CA 95014  
(408) 825-0977

ISSUED: 07/03/19

PROJECT NO: 1822 DATE: 10/16/19


PROPOSED  
FIRST  
FLOOR PLAN

**A-2.0**

PROPOSED FIRST FLOOR PLAN

1/4"

1



PROPOSED SECOND FLOOR PLAN

1/4"


1

ISSUED 07/03/19

PROJECT NO. 1822 DATE 10/16/19

PROPOSED  
SECOND  
FLOOR PLANS

A-2.1



PROPOSED LEFT ELEVATION

1/4"

2



PROPOSED FRONT ELEVATION

1/4"


1

ISSUED: 07/23/19

PROJECT NO: 1802 DATE: 10/16/19

PROPOSED  
FRONT & LEFT  
ELEVATIONS

A-3.0



PROPOSED RIGHT ELEVATION

1/4"

2



PROPOSED REAR ELEVATION

1/4"


1

ISSUED: 07/03/19

PROJECT NO: 1822 DATE: 10/16/19


PROPOSED  
REAR & RIGHT  
ELEVATIONS

A-3.1



SECTION 2-2

1/4" 2



SECTION 1-1

1/4" 1

ISSUED: 07/03/19

PROJECT NO: 1822 DATE: 10/16/19

SECTIONS

A-4.0






**BASIS OF BEARINGS**

THE BEARING N76°45'20"E OF ROBNICK AVE PER  
PM 605 M 48  
SANTA CLARA COUNTY RECORDS

**LOT AREA**

13,277 SQ. FT.±

1"=10'



**UNDERGROUND UTILITY NOTE**

ALL UNDERGROUND UTILITY LINES MAY NOT BE SHOWN HEREON, BUT MAY EXIST AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE SIZE, DEPTH, LOCATION THEREOF  
**CALL BEFORE YOU DIG**

**EASEMENTS**

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE ANY CONFLICTS WITH ANY EASEMENTS. EASEMENTS IF ANY ARE NOT INDICATED HEREON

**CITY BENCHMARK NO. 3**

THE ELEVATIONS SHOWN HEREON ARE PER CITY OF CAMPBELL BM NO. 3 BRASS DISC ON TOP CURB AT S/E CORNER OF MORE AND POLLARD AVE  
BM ELEV TAKEN AS 280.08 CITY DATUM

**T.B.M.**

TOP OF SSMH  
RIM ELEV=258.00



SHEET	1	OF	1
VAN DUSEN 18-01	SCALE: 1"=10'	PROJECT MGR: KA	DATE: 12-07-18

**TOPOGRAPHIC-BOUNDARY SITE PLAN**  
1420 VAN DUSEN LANE, CAMPBELL, CA 95008  
DOC NO. 23926057  
APN 403-19-025  
SANTA CLARA COUNTY, CALIFORNIA




**BAY LAND CONSULTING**  
LAND SURVEYORS/CIVIL ENGINEERS  
P.O. BOX 299  
SANTA CLARA, CA 95020  
PH: (408) 286-0700  
MAPPING THE BAY AREA

# ON-SITE GRADING & DRAINAGE PLANS



SCALE: 1" = 10'



### LEGEND


EXISTING	PROPOSED



<b>DESIGN EVEREST, INC.</b> <small>365 FLOWER LANE                  MOUNTAIN VIEW, CA 94043                  PHONE: (865) 311-0015</small>	Date:	Revision:	Date:	By:
	Drawn By: NGM			Check:
<b>SHEET DESCRIPTION</b> ON-SITE GRADING & DRAINAGE PLANS 1420 VAN DUSEN LN BUILDING PERMIT NO. _____	No.:			
	APN 403-19-098			
	1490 VAN DUSEN AVENUE			
SCALE: 1" = 10'				
SHEET: 3/8				

GP\_Compbell\_1420\_VAN\_DUSEN  
 1/15/2004

# COMPOSITE UTILITY & STORMWATER MGT. PLAN



CONTRACTOR TO VERIFY LOCATIONS, CONDITIONS AND CAPACITY OF ALL UTILITY CONNECTIONS TO EXISTING SERVICES. PROPOSED SERVICE LOCATIONS ARE APPROXIMATE AND SHOULD BE REROUTED TO OPTIMIZE SAFETY AND ROUTING TO ARCHITECTURE PLAN LOCATIONS FOR MECHANICAL SERVICE CONNECTIONS.

No.	Revision	Date	By	Check


Date:   
 Drawn By: NGM   
 Designed By: NGM

**DESIGN EVEREST, INC.**  
 365 FLOWER LANE  
 MOUNTAIN VIEW, CA 94043  
 PHONE: (866) 311-0015

UTILITY & STORMWATER MGT. PLAN  
 ON-SITE GRADING & DRAINAGE PLANS  
 BUILDING PERMIT NO. \_\_\_\_\_




SCALE: 1" = 10'  
 SHEET: 4/8



TYPICAL FILTER MEDIUM AREA  
 (FOR STORM WATER RETENTION AND/OR INFILTRATION SYSTEMS)

## DRAINAGE MANAGEMENT AREA MAP



The sizing, selection, and preliminary design of treatment BMPs and control measures for the site named below, meet the requirements of the City of Campbell's NPDES permit, No. 01-119, Provision C.3.

Date: 05/22/2019  
 Project Location/Name: 1420 Van Dusen Ln.  
 Project APN #: 403-19-025  
 Responsible Engineer: Nicholas G. Miller  
 License No.: C-80144  
 Expiration Date: 9/30/2020

## STORMWATER BIO-RETENTION BASIN SIZING CALCULATIONS:


VOLUME REQUIRED = 4% \* 3,000 SF = 120 C.F.  
 VOLUME PROVIDED = (30 FT \* 1.5' \* 0.75') + (30' \* 3' \* 1.5') = 164 C.F.

GP\_Campbell\_1420\_VAN\_DUSEN  
 1/15/2020

3

**Stabilized Construction Entrance/Exit**


CASQA Detail TC-1



1

**Silt Fence**

CASQA Detail SE-1




- NOTES**
1. Construct the length of each reach so that the change in base elevation along the reach does not exceed 1/3 the height of the linear barrier. In no case shall the reach length exceed 500'.
  2. The last 8'-0" of fence shall be turned up slope.
  3. Stake dimensions are nominal.
  4. Dimension may vary to fit field condition.
  5. Stakes shall be spaced at 8'-0" maximum and shall be positioned on downstream side of fence.
  6. Stakes to overlap and fence fabric to fold around each stake one full turn. Secure fabric to stake with 4 staples.
  7. Stakes shall be driven tightly together to prevent potential flow-through of sediment at joint. The tops of the stakes shall be secured with wire.
  8. For end stake, fence fabric shall be folded around two stakes one full turn and secured with 4 staples.
  9. Minimum 4 staples per stake. Dimensions shown are typical.
  10. Cross barriers shall be a minimum of 1/3 and a maximum of 1/2 the height of the linear barrier.
  11. Maintenance openings shall be constructed in a manner to ensure sediment remains behind silt fence.
  12. Joining sections shall not be placed at sump locations.
  13. Sandbag rows and layers shall be offset to eliminate gaps.

4

**Velocity Dissipation Devices**

CASQA Detail EC-10




\* Length per ABAG Design Standards

2

**Silt Fence**

CASQA Detail SE-1



**STANDARD BEST MANAGEMENT PRACTICE NOTES**

1. **Solid and Demolition Waste Management:** Provide designated waste collection areas and containers on site away from streets, gutters, storm drains, and waterways, and arrange for regular disposal. Waste containers must be watertight and covered at all times except when waste is deposited. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-3) or latest.
2. **Hazardous Waste Management:** Provide proper handling and disposal of hazardous wastes by a licensed hazardous waste material hauler. Hazardous wastes shall be stored and properly labeled in sealed containers constructed of suitable materials. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-5 to C-6) or latest.
3. **Spill Prevention and Control:** Provide proper storage areas for liquid and solid materials, including chemicals and hazardous substances. Spill control materials must be kept on site where readily accessible. Spills must be cleaned up immediately and contaminated soil disposed properly. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-7 to C-8, C-13 to C-14) or latest.
4. **Vehicle and Construction Equipment Service and Storage:** An area shall be designated for the maintenance, where on-site maintenance is required, and storage of equipment that is protected from stormwater run-on and runoff. Measures shall be provided to capture any waste oils, lubricants, or other potential pollutants and these wastes shall be properly disposed of off site. Fueling and major maintenance/repair, and washing shall be conducted off-site whenever feasible. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-9) or latest.
5. **Material Delivery, Handling and Storage:** In general, materials should not be stockpiled on site. Where temporary stockpiles are necessary and approved by the County, they shall be covered with secured plastic sheeting or tarp and located in designated areas near construction entrances and away from drainage paths and waterways. Barriers shall be provided around storage areas where materials are potentially in contact with runoff. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-11 to C-12) or latest.
6. **Handling and Disposal of Concrete and Cement:** When concrete trucks and equipment are washed on-site, concrete wastewater shall be contained in designated containers or in a temporary lined and watertight pit where wasted concrete can harden for later removal. If possible have concrete contractor remove concrete wash water from site. In no case shall fresh concrete be washed into the road right-of-way. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-15 to C-16) or latest.
7. **Pavement Construction Management:** Prevent or reduce the discharge of pollutants from paving operations, using measures to prevent run-on and runoff pollution and properly disposing of wastes. Avoid paving in the wet season and reschedule paving when rain is in the forecast. Residue from saw-cutting shall be vacuumed for proper disposal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-17 to C-18) or latest.
8. **Contaminated Soil and Water Management:** Inspections to identify contaminated soils should occur prior to construction and at regular intervals during construction. Remediating contaminated soil should occur promptly after identification and be specific to the contaminant identified, which may include hazardous waste removal. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages C-19 to C-20) or latest.
9. **Sanitary/Septic Water Management:** Temporary sanitary facilities should be located away from drainage paths, waterways, and traffic areas. Only licensed sanitary and septic waste haulers should be used. Secondary containment should be provided for all sanitary facilities. Refer to Erosion & Sediment Control Field Manual, 4th Edition (page C-21) or latest.
10. **Inspection & Maintenance:** Areas of material and equipment storage sites and temporary sanitary facilities must be inspected weekly. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.

**STANDARD EROSION CONTROL NOTES**

1. **Sediment Control Management:**
  - Tracking Prevention & Clean Up:** Activities shall be organized and measures taken as needed to prevent or minimize tracking of soil onto the public street system. A gravel or proprietary device construction entrance/exit is required for all sites. Clean up of tracked material shall be provided by means of a street sweeper prior to an approaching rain event, or at least once at the end of each workday that material is tracked, or, more frequently as determined by the County Inspector. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-31 to B-33) or latest.
  - Storm Drain Inlet and Catch Basin Inlet Protection:** All inlets within the vicinity of the project and within the project limits shall be protected with gravel bags placed around inlets or other inlet protection. At locations where exposed soils are present, staked fiber roles or staked silt fences can be used. Inlet filters are not allowed due to clogging and subsequent flooding. Refer to Erosion & Sediment Control Field Manual, 4th Edition (pages B-49 to B-51) or latest.
  - Storm Water Runoff:** No storm water runoff shall be allowed to drain into the existing and/or proposed underground storm drain system or other above ground watercourses until appropriate erosion control measures are fully installed.
  - Dust Control:** The contractor shall provide dust control in graded areas as required by providing wet suppression or chemical stabilization of exposed soils, providing for rapid clean up of sediments deposited on paved roads, furnishing construction area entrances and vehicle wash down areas, and limiting the amount of areas disturbed by clearing and earth moving operations by scheduling these activities in phases.
  - Stockpiling:** Excavated soils shall not be placed in streets or on paved areas. Borrow and temporary stockpiles shall be protected with appropriate erosion control measures (tarps, straw bales, silt fences, ect.) to ensure silt does not leave the site or enter the storm drain system or neighboring watercourses.
2. **Erosion Control:** During the rainy season, all disturbed areas must include an effective combination of erosion and sediment control. It is required that temporary erosion control measures are applied to all disturbed soil areas prior to a rain event. During the non-rainy season, erosion control measures must be applied sufficient to control wind erosion at the site.
3. **Inspection & Maintenance:** Disturbed areas of the Project's site, locations where vehicles enter or exit the site, and all erosion and sediment controls that are identified as part of the Erosion Control Plans must be inspected by the Contractor before, during, and after storm events, and at least weekly during seasonal wet periods. Problem areas shall be identified and appropriate additional and/or alternative control measures implemented immediately, within 24 hours of the problem being identified.
4. **Project Completion:** Prior to project completion and signoff by the County Inspector, all disturbed areas shall be reseeded, planted, or landscaped to minimize the potential for erosion on the subject site.
5. It shall be the Owner's/Contractor's responsibility to maintain control of the entire construction operation and to keep the entire site in compliance with the erosion control plan.
6. Erosion and sediment control best management practices shall be operable year round or until vegetation is fully established on landscaped surfaces.

Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.




Project Information



7

### Geotextiles and Mats

CASQA Detail EC-7




- NOTES:
1. Check slots to be constructed per manufacturer's specifications.
  2. Staking or staking layout per manufacturer's specifications.
  3. Install per manufacturer's recommendations.

TYPICAL INSTALLATION DETAIL

5

### Geotextiles and Mats

CASQA Detail EC-7




- NOTES:
1. Slope surface shall be free of rocks, clods, sticks and grass. Mats/blankets shall have good soil contact.
  2. Lay blankets loosely and stake or staple to maintain direct contact with the soil. Do not stretch.
  3. Install per manufacturer's recommendations.

TYPICAL INSTALLATION DETAIL

3

### Entrance/Outlet Tire Wash


CASQA Detail TC-3



1

### Fiber Rolls



CASQA Detail SE-5



8

### Storm Drain Inlet Protection

CASQA Detail SE-10





Source for Graphics: California Stormwater BMP Handbook, California Stormwater Quality Association, January 2003. Available from www.cabmphandbooks.com.

6

### Storm Drain Inlet Protection

CASQA Detail SE-10




- NOTES:
1. Intended for short-term use.
  2. Use to inhibit non-storm water flow.
  3. Allow for proper maintenance and cleanup.
  4. Bags must be removed after adjacent operation is completed.
  5. Not applicable in areas with high silt and clay without filter fabric.
- DI PROTECTION TYPE 3  
NOT TO SCALE

4

### Storm Drain Inlet Protection


CASQA Detail SE-10



2

### Concrete Waste Management

CASQA Detail WM-8



Project Information



**WORK TO BE DONE:**

EROSION CONTROL WORK CONSIST OF THE FOLLOWING WORK TO BE DONE ACCORDING TO THESE PLANS, THE CURRENT CITY OF CAMPBELL OR SANTA CLARA COUNTY AREA REGIONAL STANDARD DRAWINGS AND THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, AND PER THE CITY OF CAMPBELL AND/OR SANTA CLARA COUNTY GRADING ORDINANCE.

NOTE: THIS LIST IS PARTIAL, APPLY BMPs PER SHEETS EC1 & EC2 AS SITE CONDITIONS CHANGE AND REQUIRE ALTERNATE MEASURES TO PREVENT SOIL EROSION.


**BMP LEGEND (SEE ALSO SHEETS EC1 AND EC2)**

- SS-2 PRESERVATION OF EXISTING VEGETATION ~PEV~PEV~
- SS-3\* BONDED OR STABILIZED FIBER MATRIX (WINTER) ~M~M~
- SS-4\* HYDROSEEDING (SUMMER) ~TSP~TSP~
- WM-1 MATERIAL DELIVERY & STORAGE
- TC-1 STABILIZED CONSTRUCTION ENTRANCE
- SC-7 STREET SWEEPING AND VACUUMING
- SC-10 STORM DRAIN INLET PROTECTION
- DIRECTION OF LOT DRAINAGE →
- SE-5\*\* FIBER ROLL(S) ~F~F~

\*TEMPORARY MEASURES IF NEEDED, FIRST FOLLOW LANDSCAPE PLAN FOR PERMANENT EROSION CONTROL MEASURES FOR PLANTING AREAS

\*\*ASSES PRESERVATION OF EXISTING LANDSCAPING AND DETERMINE IF ADDITIONAL SOIL EROSION PROTECTION IS NEEDED IN THE FORM OF FIBER ROLLS OR EQUAL TO PREVENT THE MIGRATION OF SEDIMENT ON TO OTHER PROPERTIES.

# EROSION CONTROL PLAN



 DESIGN EVEREST, INC. 365 FLOWER LANE MOUNTAIN VIEW, CA 94043 PHONE: (925) 311-0015	Date: _____	Revision: _____	Date: _____	By: _____	Checked: _____
	Drawn By: NGM	Designed By: NGM			
EROSION CONTROL PLAN 1420 VAN DUSEN LN BUILDING PERMIT NO. _____					
 SCALE: 1" = 10' SHEET: 7/8					

GP\_Campbell\_1420\_VAN\_DUSEN  
 1/15/2004

**FRESH CONCRETE AND MORTAR APPLICATION**

**BEST MANAGEMENT PRACTICES FOR:**

- Masons and bricklayers
- Sidewalk construction crews
- Patio construction workers
- Construction inspectors
- General contractors
- Home builders
- Developers

- When cleaning up after driveway or sidewalk construction, wash fines onto dirt areas, not down the driveway or into the street or storm drain.
- Place hay bales or other erosion controls down-slope to capture runoff carrying mortar or cement before it reaches the storm drain.

**GENERAL BUSINESS PRACTICES**

- Both at your yard and the construction site, always store both dry and wet materials under cover, protected from rainfall and runoff.
- Protect dry materials from wind.
- Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from gutters, storm drains, rainfall, and runoff.
- Wash out concrete mixers only in designated wash-out areas in your yard, where the water will flow into containment ponds or onto dirt. Whenever possible, recycle washout by pumping back into mixers for reuse. Never dispose of washout into the street, storm drain, drainage ditches, or streams.

**STORM DRAIN POLLUTION FROM MASONRY AND PAVING**

Fresh concrete and cement-related mortars that wash into lakes, streams, or canyons are toxic to fish and the aquatic environment. Disposing of these materials to the storm drains or creeks causes serious problems and is prohibited by law.

**DURING CONSTRUCTION**

- Don't mix up more fresh concrete or cement than you will use in a day.
- Set up and operate small mixers on tarps or heavy plastic drop cloths.

**LANDSCAPING, GARDENING, AND POOL MAINTENANCE**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Landscapers
- Gardeners
- Swimming pool/spa service and repair workers
- General contractors
- Home builders
- Developers

**GENERAL BUSINESS PRACTICES**

- Protect stockpiles and landscaping materials from wind and rain by storing them under tarps or secured plastic sheeting.
- Store pesticides, fertilizers, and other chemicals indoors or in a shed or storage cabinet.
- Schedule grading and excavation projects for dry weather.
- Use temporary check dams or ditches to divert runoff away from storm drains.
- Protect storm drains with hay bales or other erosion controls.
- Revegetation is an excellent form of erosion control for any site.

**POOL/FOUNTAIN/SPA MAINTENANCE**

- Never discharge pool or spa water to a street or storm drain.

OR

- When emptying a pool or spa, let chlorine dissipate for a few days, and then recycle the water by draining it gradually onto a landscaped area.

- Contact the local sewage treatment authority. You may be able to discharge to the sanitary sewer by running a hose to a utility sink or sewer pipe cleanout junction.

- Do not use copper-based algaecides unless absolutely necessary. Control algae with chlorine or other alternatives to copper-based pool chemicals. Copper is a powerful herbicide. Sewage treatment technology cannot remove all of the metals that enter a treatment plant.

**LANDSCAPING/GARDEN MAINTENANCE**

- Use up pesticides. Rinse containers, and use rinse water as product. Dispose of rinsed containers in the trash.

- Dispose of unused pesticide as hazardous waste.
- Collect lawn and garden clippings, pruning waste, and tree trimmings. Chip if necessary, and compost.

- In communities with curbside yard waste recycling, leave clippings and pruning waste for pickup in approved bags or containers. Or, take to a landfill that accepts yard waste.

- Do not place yard waste in gutters.
- Do not blow or rake leaves, etc. into the street.

**STORM DRAIN POLLUTION FROM LANDSCAPING AND SWIMMING POOL MAINTENANCE**

Many landscaping activities deplete soils and increase the likelihood that earth and garden chemicals will runoff into the storm drains during irrigation or when it rains. Swimming pool water containing chlorine and copper-based algaecides should never be discharged to storm drains. These chemicals are toxic to aquatic life.

**HEAVY EQUIPMENT OPERATION**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Vehicle and equipment operators
- Site supervisors
- General contractors
- Home builders
- Developers

**SITE PLANNING AND PREVENTIVE VEHICLE MAINTENANCE**

- Designate one area of the construction site, well away from streams or storm drain inlets, for auto and equipment parking, refueling, and routine vehicle and equipment maintenance.
- Maintain all vehicles and heavy equipment. Inspect frequently for leaks.
- Perform major maintenance, repair jobs, vehicle and equipment washing off site.

**STORM DRAIN POLLUTION FROM HEAVY EQUIPMENT ON THE CONSTRUCTION SITE**

Poorly maintained vehicles and heavy equipment leaking fuel, oil, antifreeze or other fluids on the construction site are common sources of storm water pollution. Prevent spills and leaks by installing equipment from runoff channels, and by washing for leaks and other maintenance problems. Remove construction equipment from the site as soon as possible.

- Never hose down dirty pavement or impermeable surfaces where fluids have spilled. Use dry cleaning method (absorbent materials, cat litter, and/or rags) whenever possible. If you must use water, use just enough to keep the dust down.

- Sweep up spilled dry materials immediately. Never attempt to wash them away with water or bury them. Use as little water as possible for dust control.

- Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.

- Report significant spills to the appropriate spill response agencies immediately.

**PAINT REMOVAL**

- Chemical paint stripping residue is a hazardous waste.
- Chips and dust from marine paints or paints containing lead or tributyl tin are hazardous wastes. Dry sweep and dispose of appropriately.
- Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up and disposed as trash.
- When stripping or cleaning building exteriors with high-pressure water, block storm drains. Wash water onto a dirt area and spade into soil. Or, check with the local wastewater treatment authority to find out if you can collect (trap or vacuum) building cleaning water and dispose to the sanitary sewer.

**PAINTING AND APPLICATION OF SOLVENTS AND ADHESIVES**

**BEST MANAGEMENT PRACTICES FOR THE: PAINTING/CLEANUP**

- Painters
- Paperhangers
- Plasterers
- Graphic artists
- Dry wall crews
- Floor covering installers
- General contractors
- Home builders
- Developers

- Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.

- For water based paints, paint out brushes to the extent possible, and rinse to the sanitary sewer.
- For oil based paints, paint out brushes to the extent possible, filter and reuse thinners and solvents. Dispose of excess liquids and residue as hazardous waste.

**WHAT CAN YOU DO?**

- Recycle/reuse leftover paints whenever possible.
- Recycle excess water-based paint, or use up. Dispose of excess liquid, including shdges, as hazardous waste.
- Reuse leftover oil-based paint. Dispose of excess liquid, including shdges, as hazardous waste.

**STORM DRAIN POLLUTION FROM PAINTS, SOLVENTS, AND ADHESIVES**

All paints, solvents, and adhesives contain chemicals that are harmful to the wildlife in our creeks and Bay. Toxic chemicals may come from liquid or solid products or from cleaning residues or rags. It is especially important not to clean brushes in an area where paint residue can flow to a gutter, street, or storm drain.

**Blueprint for a Clean Bay**  
BEST MANAGEMENT PRACTICES FOR THE CONSTRUCTION INDUSTRY.

SANTA CLARA VALLEY NONPOINT SOURCE POLLUTION CONTROL PROGRAM

**EARTH MOVING ACTIVITIES**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Bulldozers, backhoe, and grading machine operators
- Dump truck drivers
- Site supervisors
- General contractors
- Home builders
- Developers

**DETECTING CONTAMINATED SOIL OR GROUNDWATER**

As you know, contaminated groundwater is a common problem in the Santa Clara Valley. It is essential that all contractors and subcontractors involved in excavation and grading know what to look for in detecting contaminated soil or groundwater, and test ponded groundwater before pumping. See Blueprint for a Clean Bay, a construction best management practices guide available from the Santa Clara Valley Nonpoint Source Pollution Control Program, for details.

**WATCH FOR ANY OF THESE CONDITIONS:**

- Unusual soil conditions, discoloration, or odor
- Abandoned underground tanks
- Abandoned wells
- Buried barrels, debris, or trash

**STORM DRAIN POLLUTION FROM EARTH-MOVING ACTIVITIES**

Soil excavation and grading operations loosen large amounts of soil that can flow or blow into storm drains if handled improperly. Soil erodes due to a combination of decreased soil stability, increased runoff, and increased flow velocity. Some of the most effective erosion control practices reduce the amount of runoff eroding a site and slow the flow with check dams or roughened ground surfaces.

**GENERAL BUSINESS PRACTICES**

- Schedule excavation and grading work for dry weather.
- Perform major equipment repairs away from the job site.
- When refueling or vehicle/equipment maintenance must be done on site, designate a location away from storm drains.
- Do not use diesel oil to lubricate equipment or parts.

**ROADWORK AND PAVING**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Road Crews
- Driveway/sidewalk/parking lot construction crews
- Seal coat contractors
- Operators of grading equipment paving machines dump trucks concrete mixers
- Construction inspectors
- General contractors
- Developers

**WHAT CAN YOU DO?**

- Develop and implement erosion/sediment control plans for embankment construction.
- Schedule excavation and grading work for dry weather.
- Check for and repair leaking equipment.
- Perform major equipment repairs in designated areas at your yard, away from the construction site.

**GENERAL BUSINESS PRACTICES**

- When refueling or vehicle/equipment maintenance must be done on site, designate a location away from storm drains and creeks.
- Do not use diesel oil to lubricate equipment or parts.
- Recycle used oil, concrete, broken asphalt, etc. whenever possible.

**DURING CONSTRUCTION**

- Avoid paving and seal coating in wet weather, or when rain is forecast before fresh pavement will have time to cure.
- Cover and seal catch basins and manholes when applying seal coat, slurry seal, fog seal, etc.
- Use check dams, ditches, or berms to divert runoff around excavations.

**GENERAL CONSTRUCTION AND SITE SUPERVISION**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Construction industry

**WHAT CAN YOU DO?**

- Designate one area of the site for auto parking, vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets, and bermed if necessary. Make major repairs off site.
- Cover stockpiles (asphalt, sand, etc.) and other materials with plastic tarps. Protect from rainfall and prevent runoff with temporary roofs or plastic sheets and berms.
- Catch drips from paver with drip pans or absorbent material (sorb, rags, etc.) placed under machine when not in use.
- Clean up all spills and leaks using "dry" methods (with absorbent materials and/or rags), or dig up and remove contaminated soil.
- Collect and recycle or appropriately dispose of excess abrasive gravel or sand.
- Avoid over application by water trucks for dust control.

**ASPHALT/CONCRETE REMOVAL**

- Avoid creating excess dust when breaking asphalt or concrete.
- After breaking old pavement, be sure to remove all chunks and pieces.
- Make sure broken pavement does not come in contact with rainfall or runoff.
- Shovel or vacuum saw-cut slurry and remove from the site. Cover or barricade storm drain during saw-cutting if necessary.
- Never hose down streets to clean up tracked dirt.

**STORM DRAIN POLLUTION FROM ROADWORK**

Road paving, surfacing, and pavement removal happens right in the street, where there are numerous opportunities for storm drain contamination by asphalt, saw cut slurry, or excavated material. Extra planning is required to save and dispose of materials properly and guard against pollution of storm drains and creeks.

**MATERIALS/WASTE/HANDLING**

**BEST MANAGEMENT PRACTICES FOR THE:**

- Practice Source Reduction - minimize waste when you order materials. Order only the amount you need to finish the job.
- Use recyclable materials whenever possible.
- Dispose of all wastes properly. Many construction materials and wastes, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation can be recycled. (See the references list of recyclers at the back of Blueprint for a Clean Bay.) Materials that cannot be recycled must be taken to an appropriate landfill or disposed of as hazardous waste. Never bury waste materials or leave them in the street or near a creek or stream.

**STORM DRAIN POLLUTION FROM CONSTRUCTION ACTIVITIES**

Construction sites are common sources of storm-water pollution. Materials and wastes that blow or wash into a storm drain, gutter or street have a direct impact on local creeks and the Bay. As a contractor, site supervisor, owner or operator of a site, you may be responsible for any environmental damage caused by your subcontractors or employees.

- Cover and maintain dumpsters. Check frequently for leaks. Place dumpsters under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. Never clean a dumpster by hosing it down on the construction site.
- Make sure portable toilets are in good working order. Check frequently for leaks.

**BEST MANAGEMENT PRACTICES FOR STORM WATER POLLUTION PREVENTION**

**Spill Response Agencies**

1. Dial 911
2. Santa Clara Valley Water District Environmental Compliance Division (408) 927-0711.
3. Governor's Office of Emergency Services, Warning Center (800) 852-7550 (24 hours).

**Local Pollution Control Agencies**

- Santa Clara County Office of Toxics and Solid Waste Management (408) 441-1195
- Santa Clara Valley Water District (408) 927-0710
- San Jose/Santa Clara Water Pollution Control Plant (408) 945-5300
- Serving Campbell, Cupertino, Los Gatos, Milpitas, Monte Sereno, San Jose, Santa Clara and Saratoga
- Sunnyvale Water Pollution Control Plant (408) 730-7270
- Palo Alto Regional Water Quality Control Plant (415) 320-2508
- Serving East Palo Alto, Los Altos, Los Altos Hills, Menlo Park, Palo Alto, and Stanford

Note: The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site. Owner and contractor may be held responsible for any environmental damage caused by the subcontractors or employees.

**ORDINANCE OF THE CITY OF CAMPBELL ESTABLISHING REQUIREMENTS FOR STORM WATER POLLUTION CONTROL**

- A. Criminal Penalties.** Any person who violates any provision of this article shall be guilty of a misdemeanor and upon conviction thereof shall be punishable by imprisonment for a term not to exceed six (6) months or by a fine not to exceed \$1000 or by both. Each and every violation of this chapter shall constitute a separate offense. Every day each such violation continues shall be an additional offense.
- B. Civil Penalties.** Any person who violates any provision of this chapter shall be civilly liable to the City of Campbell for all costs, including attorneys fees, associated with the investigation and remediation of environmental conditions caused by the discharge of pollutants into the Municipal Storm Drain System or a Watercourse in violation of this chapter.
- C. Civil Liability.** Any person who violates any provision of this chapter shall be civilly liable to the City of Campbell for all costs, including attorneys fees, associated with the investigation and remediation of environmental conditions caused by the discharge of pollutants into the Municipal Storm Drain System or a Watercourse in violation of this chapter.
- D. Remedies Cumulative.** The remedies provided for in this chapter are cumulative and not exclusive and shall be in addition to any and all other remedies available to the City of Campbell under State and Federal Law.

Checked By:	
Date:	
Revised:	
No.:	
Date:	07/07/03
Drawn By:	
Designed By:	

PLAN FOR THE IMPROVEMENT OF  
**BLUEPRINT FOR A CLEAN BAY**  
ENCROACHMENT PERMIT NO.

SCALE:  
N.T.S.

SHEET:  
OF

**PLANT LEGEND AND NOTES**

Symbol	Species	Size	Water	WUCOLS
	Tulbepha violacea @ 30" ac	1 gallon	low	3
	Erigeron karwinskianus/ Santa Barbara Daisy @ 30" ac	1 gallon	low	3
	Carex alba/ Berkeley Sedge @ 36" ac	1 gallon	low	3
A	Pittosporum tenuifolium	5 gallon	low	3
B	Cotinus Royal Purple/ Smoke Tree	15 gallon	low	3
C	Chondropetalum Suzans	5 gallon	low	3
D	Chondropetalum tacsonum/ Cape Rush	5 gallon	low	3
E	Eucalyptus japonica	5 gallon	low	3
F	Pittosporum Woodens Dwarf	5 gallon	low	3
G	Lavandula Procea	5 gallon	low	3
H	Lavandula Grosso/ Lavender	5 gallon	low	3
I	Cotinus Golden Spark/ Smoke Tree	5 gallon	low	3
T1	Prunus serrulata Kwanzan/ Cherry	24" box wood		3

**PROJECT INFORMATION**

The proposed front yard landscape area is under 2500 sq. ft., thus Prescriptive Compliance with the local WUCOLS has been selected.

Applicant: Charles Zhang  
 Project Address: 1420 Van Dusen Lane  
 Total Landscape Area: 1775 sq ft  
 Project Type: New  
 Water Supply: Potable  
 \*I agree to comply with the requirements of the prescriptive compliance option for the MWELCO\*

Architect: \_\_\_\_\_ Date: \_\_\_\_\_

**PLANNING FINAL REQUIRED**  
 THE NEW LANDSCAPING INDICATED ON THE PLANS MUST BE INSTALLED PRIOR TO FINAL INSPECTION. CHANGES TO THE LANDSCAPING PLAN REQUIRE PLANNING APPROVAL.

- 1) 100% of the proposed plant material have an average WUCOLS rating of 3 or less.
- 2) There is no proposed turf.
- 3) No lawn is proposed on a slope which exceeds 1" vertical elevation change in 4'.
- 4) No lawn is proposed in a parking strip.

- 1) Verify placement of all proposed plants.
- 2) Protect existing trees to remain. Verify placement of tree protection fences.
- 3) Thoroughly prepare soil prior to planting. The contractor shall submit a soil sample for analysis to a local lab for analysis and recommendations for soil preparation prior to planting.
- 4) Incorporate 4 cu. of compost per 1000 sq. ft. into rubber soil.
- 5) Spread 3" of certified mulch, Prochip or equal, after planting.
- 6) I have complied with the criteria of the water efficient landscape ordinance and applied them for the efficient use of water in the landscape design.




TULBAGHA ERIGERON CAREX



PITOSPORIUM COTINUS LAVANDRA CHONDROPETALUM ELIONYALIS



PITOSPORIUM LAVANDRA LAVANDULA COTINUS PRUNUS



W. Jeffrey Heid  
 Landscape Architect  
 C-2235

6179 Orinda Drive  
 San Jose, California 95123  
 tel 408 691-9207  
 fax 408 226-6005  
 email wjheid@aol.com

OWNERSHIP AND USE OF DRAWINGS  
 All drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain the property. They are to be used only with respect to the Project and are not to be used on any other project. Distribution or disclosure to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect. Common law copyright or other reserved rights.

REVISED 4/28/19



ZHANG RESIDENCE

for:  
 CHARLES ZHANG  
 1420 VAN DUSEN LANE  
 CAMPBELL, CA. 95008

MASTER PLANTING PLAN

date: 4/25/19  
 scale: NOTED  
 drawn by: W.J.H.  
 job no.: 21921  
 sheet:


L I  
 of 416



**IRRIGATION LEGEND**

-  Hunter I-Core Weatherbased controller with Solar Sync and rain sensor - verify placement in garage. Controller shall have battery backup for programming.
-  Felco #765 - 1" pressure vacuum breaker provide lockable cover - verify location point of connection and install per manufacturer's specifications.
-  1" schedule 40 pvc mainline - min. depth 18"
-  Rainbird PEP series control valves with in line pressure reducer set to 35 psi and Y filter for drip circuits - install below grade in valve box, maximum two valves per box.
-  Schedule 40 pvc lateral lines - min. depth 12" - all lines 3/4" unless otherwise noted.
-  Rainbird, or equal, 1 gph pressure compensating emitters (2 per one gallon plan, 3 per five gallon, 4 per 15 gallon set on 3/4" drip line - set drip line on ground surface and cover with final mulch.
-  Control valve number.


- 1) Verify water source and placement of backflow preventer.
- 2) Verify site water pressure at 65 psi - notify architect prior to construction if found to be different.
- 3) Verify controller in garage and control wire runs.
- 4) Verify operation of system before backfilling trenches. Drip line to be secured to grade with stakes and covered with final mulch.
- 5) System layout is diagrammatic, actual field conditions will dictate final layout, addition of drip line, etc.
- 6) Verify control wire placement and operation of valves.
- 7) Contractor shall be responsible for setting and monitoring irrigation system to apply adequate water for establishment, but to eliminate runoff and soil saturation.
- 8) Contractor to submit maintenance and irrigation schedule to owner at completion of installation and maintenance/warranty period.
- 9) Contractor shall verify location of all underground utilities prior to any trenching or excavation.
- 10) Contractor shall provide all necessary safety precautions throughout construction. This shall include signage and barriers.
- 11) I have complied with the criteria of the local WELO and applied them for the efficient use of water in the design of the irrigation system.
- 12) Pressure regulators shall be used as needed to ensure a consistent dynamic pressure range throughout the system.
- 13) Locate a manual shut off valve between the backflow valve and water meter.
- 14) All irrigation equipment and emission devices shall meet the requirements set in the ANSI standard ASABE/ ICC 902-2014.
- 15) At the time of final inspection, the permit applicant must provide the owner of the property with a certificate of completion, certificate of installation, irrigation schedule and a schedule of landscape and irrigation maintenance.



- 1 SINGLE-OUTLET BARB INLET X BARB OUTLET EMITTER:  
RAIN BIRD XERI-BUG EMITTER
- 2 5/8" POLYETHYLENE TUBING:  
RAIN BIRD XF-SERIES TUBING OR  
RAIN BIRD XT-700 XERI-TUBE OR  
RAIN BIRD XBS BLACK STRIPE TUBING
- 3 FINISH GRADE

- NOTES:
1. USE RAIN BIRD XERIMAN TOOL XM-TOOL TO INSERT EMITTER DIRECTLY INTO 5/8" POLYETHYLENE TUBING.
  2. RAIN BIRD XERI-BUG BARB X BARB EMITTERS ARE AVAILABLE IN THE FOLLOWING MODELS:  
XB-05PC 0.5 GPH XB-10PC 1.0 GPH XB-20PC 2.0 GPH

**A** XERI-BUG INTO 1/2-INCH TUBING  
N.T.S. OPTION 1 1=1/8"=10



**IRRIGATION PLAN**  
1/8" = 1'-0"

W. Jeffrey Heid  
Landscape Architect  
C-2235

6179 Orinda Drive  
San Jose, California 95123

tel 408 691-9207  
fax 408 226-6005  
email wjheid@comcast.net

OWNERSHIP AND USE OF DRAWINGS  
All drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain the property. They are to be used only with respect to the Project and are not to be used on any other project. Distribution or duplication to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as authorization in derogation of W. Jeffrey Heid Landscape Architect. Common law, copyright or other reserved rights.



ZHANG RESIDENCE

for:  
CHARLES ZHANG  
1420 VAN DUSEN LANE  
CAMPBELL, CA. 95008

IRRIGATION PLAN

date: 4/28/19  
scale: NOTED  
drawn by: W.J.H.  
job no.: 21921  
sheet:

L 3  
of 416